

9630-753

Heat Pump Zone Control Box with Time Delay Relay

Note: Install this kit per the installation instructions shown for 9630A752. Installation and operation is identical except for the time delay feature included in this control kit.

Use the time delay feature of this control kit to delay compressor operation on initial application of high voltage to the unit and to "stagger" compressor starting of multiple units when high voltage is applied.

If a time delay is desired, before installation of control box, remove control box lid and set the switch(es) on the timer relay to the desired delay time interval. Multiple units should use differing time intervals - example 8, 16 and 24 seconds could be used for a three unit installation.

Be aware that the control box time delay will be added to the delay present between cycles of the thermostat.

RV Products, a division of Airxcel, Inc.

P.O. Box 4020

Wichita, KS 67204

1976-694 (3-15) PP