



INTERNATIONAL THERMAL RESEARCH

HYDRONIC HEATING SYSTEM MAINTENANCE AND

For Technical Service and Parts:

USA call 1-800-993-4402

CANADA call 1-800-755-1272

Recommended Service and Maintenance Schedule

A	Rubber hoses – fuel, water and coolant	Annually	Inspect all hoses for cracks, leaks weak points, and corrosion. Replace if necessary
B	Hose clamps	Annually	Inspect for hose wear under clamps, and corrosion. Replace if necessary
C	Fuel filter	Annually	Replace
D	Nozzle/O-ring/Filter	Annually	Disassemble, clean, inspect for wear, replace filter and nozzle O-Ring
E	Ignitor	Annually	Inspect for wear. Replace after 2 years
F	Exhaust System	Annually	Inspect for leaks, corrosion, tighten joints as necessary
G	Coolant	Annually 36 Mths	Check level and PH
			Replace
H	Electronic Control board	Annually	Ensure connections are tight and not corroded
I	Compressor, Fuel Pump, Combustion Fan	Annually	Inspect hoses for cracks and leaks. Replace if necessary. Inspect fan for corrosion and wear
J	Combustion chamber and exhaust	1000 hours	Vacuum clean

See Owners Manual for additional service and maintenance information

Service Kits part #'s

Hurricane Annual Service Kit	2150	
Inc. Ignitor, Garber fuel filter, Compressor air filter, Nozzle filter, Nozzle o-ring		
Hurricane 3 year service kit	2151	
Inc. Ignitor, Garber fuel filter, Compressor air filter, Nozzle filter, Nozzle o-ring, Digital flame sensor		
Hurricane 5 year service kit	2152	
Inc. Ignitor, Garber fuel filter, Compressor air filter, Nozzle filter, Nozzle o-ring, Digital flame sensor, Nozzle		

In-Service date

Serial no.

See label located on top of heater

**Service Date /
hours on meter**

**Services
Performed**

**Technician /
Service Centre**

